

CITY OF RIVERSIDE
PUBLIC UTILITIES
WATER DIVISION

CWD STANDARD DRAWINGS, 2004




MARCH 2004

INDEX


CWD-010-1	TYPICAL PLAN LAYOUT, SHT 1 OF 2
CWD-010-2	TYPICAL PLAN LAYOUT, SHT 2 OF 2
CWD-015-1	WATER MAIN AND SANITARY SEWER SEPARATION, CASE 1
CWD-015-2	WATER MAIN AND SANITARY SEWER SEPARATION, CASE 2
CWD-015-3	WATER MAIN AND SANITARY SEWER SEPARATION, NOTES
CWD-023-1	STRUCTURE INTERFERENCE – TYPE A, B OR C ENCASEMENT
CWD-023-2	STRUCTURE INTERFERENCE – ENCASEMENT SECTIONS
CWD-030	THRUST BLOCK DETAILS – TYPICAL
CWD-040-1	TYPICAL PIPE TRENCH, BEDDING, BACKFILL AND PAVEMENT REQUIREMENTS
CWD-040-2	TYPICAL PIPE TRENCH, BEDDING, BACKFILL AND PAVEMENT REQUIREMENTS – GENERAL NOTES
CWD-220	TYPICAL SPLIT BUTT STRAP – 8” THROUGH 42” DIAMETER (150 PSI DESIGN PRESSURE)
CWD-300	TYPICAL FLANGED OUTLET – 4” THROUGH 20”
CWD-320	TYPICAL FLANGED TANGENT OUTLET – 4” THROUGH 12” DIAMETER
CWD-340	TYPICAL THREADED OUTLET – 1” THRU 2 ½” DIAMETER
CWD-350	TYPICAL MANWAY FOR LARGE PIPELINES
CWD-408	6” HYDRANT HEAD BLOW-OFF ML&C STEEL BURY – 24” MAIN AND SMALLER
CWD-409	6” HYDRANT HEAD BLOW-OFF DI BURY – 24” MAIN AND SMALLER
CWD-410-A	8” BLOW-OFF BELOW GRADE WITH LESS THAN 10’ OF COVER
CWD-410-B	8” BLOW-OFF BELOW GRADE WITH MORE THAN 10’ OF COVER
CWD-411-A	TYPICAL 2” BLOW-OFF ASSEMBLY FOR MAINS WITH LESS THAN 42” OF COVER
CWD-411-B	TYPICAL 2” BLOW-OFF ASSEMBLY FOR MAINS WITH MORE THAN 42” OF COVER
CWD-412	6” THROUGH 10” TEMPORARY CONSTRUCTION END CAPS FOR FLUSHING, TESTING & CHLORINATION
CWD-413	12” TEMPORARY CONSTRUCTION END CAP FOR FLUSHING, TESTING & CHLORINATION
CWD-432	TEMPORARY WATER SAMPLER
CWD-433	WATER QUALITY SAMPLING STATION
CWD-451	TYPICAL 2” AIR VALVE INSTALLATION
CWD-460	TYPICAL 4” AIR VALVE INSTALLATION

CWD-462	TYPICAL 6" AIR VALVE INSTALLATION
CWD-465	TYPICAL 8" AIR VALVE INSTALLATION
CWD-500	TYPICAL VALVE BOX FOR GATE VALVES
CWD-504	TAPPING SLEEVE AND TAPPING VALVE DETAIL FOR DOMESTIC AND FIRE SERVICES
CWD-510	TYPICAL VALVE BOX FOR BUTTERFLY VALVES
CWD-515	TYPICAL SPLIT-SLEEVE LINER AND CAP FOR 8" AND 10" BOX
CWD-570	TYPICAL CONDUIT SUPPORT
CWD-600	1-INCH WATER SERVICE
CWD-601	2-INCH WATER SERVICE
CWD-615	4" THRU 10" ABOVE GROUND FIRE SERVICE
CWD-620-1	3", 4" AND 6" COMPOUND METER WATER SERVICE
CWD-620-2	BILL OF MATERIALS FOR 3", 4" AND 6" COMPOUND METER WATER SERVICE
CWD-621-1	FMCT WATER SERVICE
CWD-621-2	BILL OF MATERIALS FOR 8" FMCT WATER SERVICE
CWD-622-1	10" DOMESTIC WATER SERVICE
CWD-622-2	BILL OF MATERIALS FOR 10" COMPOUND WATER SERVICE
CWD-700	REGULAR AND SUPER FIRE HYDRANT DETAIL
CWD-800	NON-TRAFFIC VAULT FOR 3" THRU 6" COMPOUND METERS
CWD-801	NON-TRAFFIC VAULT FOR 8" COMPOUND METERS
CWD-802	NON-TRAFFIC VAULT FOR 10" COMPOUND METERS
CWD-811	BLOW-OFF MANHOLE INSTALLATION
CWD-816	MANHOLE DETAIL – 48" MAX ID PIPE
CWD-900-A	4" DIA. GUARD POST INSTALLATION
CWD-900-B	2.5" DIA. GUARD POST INSTALLATION
CWD-922	TEST LEAD INSTALLATION
CWD-923	FLANGE INSULATION AND TEST LEAD INSTALLATION
CWD-924	JOINT BOND DETAILS
CWD-960-1	NOTIFICATION SIGN
CWD-960-2	NOTIFICATION SIGN

DRAWN	DATE	CHECK	APPROV.	DRAWN	DATE	CHECK	APPROV.	DRAWN	DATE	CHECK	APPROV.
0	WEF	03-04		1				2			
								3			

LEGEND

	New Ductile Iron Pipe		Exist Service
	Tract Boundary		Exist FH
	Tap Sleeve w/Tap GV		Exist Valve
	Gate Valve		Electrical UG
	New Cap w/Blow-Off		St Light Conduit
	New Ell		Telephone UG
	New Tee		Sewer
	New Cross		Gas
	New FH		Storm Drain
	Exist Pipe		New Service
	Exist Service		New Service (to be locked off)
	Exist FH		New Service (by City)
	Exist Valve		New Landscape Service (by City)
	Electrical UG		
	St Light Conduit		
	Telephone UG		
	Sewer		
	Gas		
	Storm Drain		
	New Service		
	New Service (to be locked off)		
	New Service (by City)		
	New Landscape Service (by City)		



"FULL" PAD ELEVATION
TYPICAL ALL LOTS

Note:
Profile required for
Water Mains $\geq 12"$ Dia.

PLAN

BILL OF MATERIALS			
SYMBOL	ITEM	MAIN	FH

TWO DAYS BEFORE YOU DIG
CALL Underground Service Alert
TOLL FREE: 1-800-227-2600

BENCH MARK:

DEVELOPER NAME: _____
CITY OF RIVERSIDE
WATER SYSTEM
APPROVED BY _____ DATE _____
VOID ONE YEAR FROM THIS DATE


ENGINEERS
SEAL

ENGINEERS BLOCK
SHALL INCLUDE:
Address _____
Telephone No. _____
Engineer _____ RCE# _____

PIPE CURVE DATA			
R	Δ	L	T
①			
②			
③			

GENERAL NOTES

- 1.) GENERAL NOTES TO BE SUBMITTED AT FIRST PLAN CHECK
- 2.) SCALE OF THE DRAWINGS SHALL BE 1" = 40'.
- 3.) SIZE OF DRAWINGS SHALL BE "SIZE 5" - 22" X 34" OR 24" X 36".
- 4.) REFERENCE SECTION 2-3.
- 5.) CAD REFERENCE, EXAMPLE TITLE SHEET: G:\WATER\ACAD\COMMON\Drafting Stds\CITY14.dwg



LOCATION MAP

(Include Index Map if more than 1 sheet)

e.g.:
• Section View of Undercrossing
• Section View of Overcrossing
• System Connection
DETAILS
(As Required)

STANDARD CITY OF RIVERSIDE
PUBLIC UTILITIES TITLE BLOCK
(N7S)

NOTE: THIS SYSTEM SERVED BY _____ ZONE

TITLE

CITY OF RIVERSIDE
DEPARTMENT OF PUBLIC UTILITIES
DRAWING NO. **W**
DIV. _____ SHT X OF X

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL PLAN LAYOUT
SHT 1 OF 2

 CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING | DATE: MAR 2004 | CWD-010-2

APPROV.	CHECK	DATE	DRAWN	DATE	CHECK	APPROV.	3
APPROV.	CHECK	DATE	DRAWN	DATE	CHECK	APPROV.	2
APPROV.	CHECK	DATE	DRAWN	DATE	CHECK	APPROV.	1
APPROV.	CHECK	DATE	DRAWN	DATE	CHECK	APPROV.	0
DATE	03-04	WEF					

INSTALLATION OF NEW SANITARY SEWER




FIGURE 1 - PARALLEL CONSTRUCTION




FIGURE 2 - CROSSINGS

MINIMUM SEPARATION REQUIREMENTS FOR WATER MAIN AND SEWER LINE CONSTRUCTION PER SECTION 64572 (WATER MAIN SEPARATION, CALIFORNIA WATERWORKS STANDARDS, TITLE 22, CALIFORNIA CODE OF REGULATIONS.)

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

WATER MAIN AND SANITARY SEWER
SEPARATION
CASE 1



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004

CWD-015-1

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0

INSTALLATION OF NEW WATER MAIN




FIGURE 1 - PARALLEL CONSTRUCTION




FIGURE 2 - CROSSINGS

NEW WATER MAIN - EXISTING SANITARY SEWERLINE

MINIMUM SEPARATION REQUIREMENTS FOR WATER MAIN AND SEWERLINE CONSTRUCTION
PER SECTION 64572 (WATER MAIN SEPARATION, CALIFORNIA WATERWORKS STANDARDS,
TITLE 22, CALIFORNIA CODE OF REGULATIONS.)

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS



WATER MAIN AND SANITARY SEWER
SEPARATION
CASE 2



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004


CWD-015-2

0	DRAWN WEF	DATE 03-04	CHECK	APPROV. 	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.										
<p style="text-align: center;">WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS</p>										<p style="text-align: center;">WATER MAIN AND SANITARY SEWER SEPARATION NOTES</p>																			
<p> CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING</p>																				<p>DATE: MAR 2004</p>				<p>CWD-015-3</p>					

NOTES AND DEFINITIONS

1. HEALTH AGENCY -- THE DEPARTMENT OF HEALTH SERVICES. FOR THOSE WATER SYSTEMS SUPPLYING FEWER THAN 200 SERVICE CONNECTIONS, THE LOCAL HEALTH OFFICER SHALL ACT FOR THE DEPARTMENT OF HEALTH SERVICES.
2. WATER SUPPLIER -- "PERSON OPERATING A PUBLIC WATER SYSTEM" OR "SUPPLIER OF WATER" MEANS ANY PERSON WHO OWNS OR OPERATES A PUBLIC WATER SYSTEM.
3. LOW HEAD WATER MAIN -- ANY WATER MAIN WHICH HAS A PRESSURE OF FIVE PSI (POUNDS PER SQUARE INCH) OR LESS AT ANY TIME AT ANY POINT IN THE MAIN.
4. DIMENSIONS ARE FROM THE OUTSIDE OF WATER MAIN TO THE OUTSIDE OF SANITARY SEWER LINE OR MANHOLE.
5. COMPRESSION JOINT -- A PUSH-ON JOINT THAT SEALS BY MEANS OF THE COMPRESSION OF A RUBBER RING OR GASKET BETWEEN THE PIPE AND A BELL OR COUPLING.
6. MECHANICAL JOINTS -- BOLTED JOINTS.
7. RATED WORKING WATER PRESSURE OR PRESSURE CLASS -- A PIPE CLASSIFICATION SYSTEM BASED UPON INTERNAL WORKING PRESSURE OF THE FLUID IN THE PIPE, TYPE OF PIPE MATERIAL, AND THE THICKNESS OF THE PIPE WALL.
8. FUSED JOINT -- THE JOINING OF SECTIONS OF PIPE USING THERMAL OR CHEMICAL BONDING PROCESSES.
9. SLEEVE -- A PROTECTIVE TUBE OF STEEL WITH A WALL THICKNESS OF NOT LESS THAN ONE-FOURTH INCH INTO WHICH A PIPE IS INSERTED.
10. GROUND WATER -- SUBSURFACE WATER FOUND IN THE PART OF THE GROUND THAT IS WHOLLY SATURATED.
11. HOUSE LATERAL -- A SANITARY SEWER CONNECTING THE HOUSE LATERAL DRAIN, BUILDING DRAIN, AND THE MAIN SANITARY SEWERLINE.


APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0



TYPE A OR B ENCASEMENT FOR WATER & SEWER
REQUIRED TO SPAN TRENCH, OR WHERE ENCASEMENT IS NOT POURED ON UNDISTURBED EARTH

NOTE:

- ① EXTEND MACHINED PIPE ENDS BEYOND ENCASEMENT
- ② SEE CWD-023-2 FOR CROSS-SECTION OF A, B, OR C ENCASEMENT DETAIL




TYPE C ENCASEMENT FOR WATER & SEWER


WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

STRUCTURE INTERFERENCE
TYPE A, B, OR C ENCASEMENT




[illegible]

TYPE A - PIPE CASING
SECTION A



TYPE B - REINFORCED ENCASEMENT

SECTION B



TYPE C - PLAIN ENCASEMENT
SECTION C

GENERAL NOTES

- 1.) ALL MATERIALS OF CONSTRUCTION SHALL CONFORM TO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION"

APPROV.: CHECK DATE DRAWN 3	APPROV.: CHECK DATE DRAWN 2	APPROV.: CHECK DATE DRAWN 1	APPROV.: CHECK DATE DRAWN 0	DATE 03-04	DRAWN WEF	<p style="text-align: center;"><u>TEE</u></p>	<p style="text-align: center;"><u>CROSS</u></p>	<p style="text-align: center;"><u>ELL</u></p>
						<p style="text-align: center;"><u>ANCHORAGE OF VALVE</u></p>	<p style="text-align: center;"><u>REDUCER</u></p>	<p style="text-align: center;"><u>VERTICAL P.I.</u></p>
						<p><u>GUIDELINE</u></p> <p><u>NOTES:</u></p> <ol style="list-style-type: none"> 1.) ALL MATERIALS OF CONSTRUCTION SHALL CONFORM TO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION". 2.) THRUST AND ANCHOR BLOCKS FOR D.I.P. AND M.L.&C. STEEL PIPE SHALL BE OF PCC 450-C-2000 CONCRETE AND SHALL BE POURED AGAINST UNDISTURBED SOIL. CONCRETE SHALL BE KEPT CLEAR OF THE BELL END OF FITTINGS FOR DUCTILE IRON PIPE. 3.) ENGINEERED-APPROVED RESTRAINED JOINTS MAY BE USED IN-LIEU OF THRUST BLOCKS. 4.) ANCHOR BLOCK FOR GATE VALVES SHALL BE KEYED A MINIMUM OF 12 INCHES INTO TRENCH WALL AND 6 INCHES INTO BOTTOM OF TRENCH. 5.) THE ENGINEER OF RECORD SHALL SIZE ALL THRUST BLOCKS ON THE BASIS OF THE SOIL PASSIVE PRESSURE. 		
						<p>WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS</p>		

1" AC SURFACE COURSE
TYPE (D2-AR-4000) PER
STANDARD SPECIFICATION
FOR PUBLIC WORKS
CONSTRUCTION

CL WATER MAIN

AC BASE COURSE
TYPE (C2-AR-4000) PER
STANDARD SPECIFICATION
FOR PUBLIC WORKS
CONSTRUCTION
FLUSH TO THE
EXISTING PAVEMENT

12' MIN

DRIVING LANE

6"

FEATHER
TO MEET
EXISTING
PAVEMENT

EXISTING PAVEMENT

95% RELATIVE COMPACTION

95% RELATIVE COMPACTION

6"

BASE COURSE,
SEE NOTES #5 AND
#6 IN CWD-040-2,
AND SPECIFICATIONS

VARIES

90% RELATIVE COMPACTION

BACKFILL MATERIAL

12" MIN.

WATER PIPELINE

BEDDING

90% RELATIVE COMPACTION

4" MIN.

BOTTOM OF PIPE GRADE

EXTEND BEDDING TO
6" MIN BELOW THE
BOTTOM OF THE PIPE
IF THE TRENCH IS
IN ROCKY GROUND


SEE NOTE #1, CWD-040-2

MAX TRENCH WIDTH = OD PIPE + 36"

SUBGRADE,
SEE NOTE #7,
CWD-040-2, FOR
OVER-EXCAVATION
REQUIREMENTS

TYPICAL TRENCH SECTION

SEE CWD-040-2 FOR NOTES

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0
<p>GENERAL NOTES:</p> <ol style="list-style-type: none"> 1.) MINIMUM TRENCH WIDTH = OD + 12" FOR 4" TO 12" NOMINAL DIAMETER PIPE AND OD + 18" FOR GREATER THAN 12" NOMINAL DIAMETER PIPE. 2.) THE MATERIAL FOR BEDDING SHALL BE COHESIONLESS SANDY LOAM, SAND, OR SANDY GRAVEL MATERIAL OBTAINED FROM PROJECT EXCAVATION OR FROM APPROVED BORROW AREAS. THE BEDDING MATERIAL SHALL NOT CONTAIN ANY ROCKS OR OTHER MATERIAL DELETERIOUS TO THE PIPE. 3.) SAND BEDDING SHALL BE USED WHEN THE SAND EQUIVALENT OF THE NATIVE MATERIAL IS LESS THAN 30, PER ASTM D2419. 4.) FOR PAVED AND UNPAVED AREAS, THE COMPACTION OF BEDDING AND BACKFILL MATERIALS AND PAVEMENT REPLACEMENT SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION "GREEN BOOK" LATEST EDITION. 5.) COMPACTED BACKFILL MATERIAL IN THE UNPAVED AREAS SHALL COMPLY WITH THE SAME REQUIREMENTS AS THE BACKFILL MATERIAL COMPACTION IN THE STREETS. 6.) THE BASE COURSE MATERIAL SHALL BE CRUSHED AGGREGATE BASE MATERIAL AS SPECIFIED IN SECTION 200-2 "UNTREATED BASE MATERIALS" OF THE CONSTRUCTION SPECIFICATIONS. 7.) IF THE ENGINEER DETERMINES THAT THE SOIL UPON WHICH THE PIPE IS TO BE PLACED IS UNSTABLE, THE CONTRACTOR SHALL OVER-EXCAVATE THE BOTTOM OF THE TRENCH TO A DEPTH OF 12" OR AS DIRECTED BY THE ENGINEER AND PLACE A LAYER OF CRUSHED ROCK ON THE TRENCH SUBGRADE COMPACTED TO 90% RELATIVE COMPACTION. 8.) THE BACKFILL AND PAVING SHALL COMPLY WITH THE CONSTRUCTION SPECIFICATIONS. THE BACKFILL AND PAVING MAY VARY ACCORDING TO AGENCY REQUIREMENTS. 																			
<p>WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS</p>										<p>TYPICAL PIPE TRENCH, BEDDING, BACKFILL AND PAVEMENT REQUIREMENTS (GENERAL NOTES)</p>									
 CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING										<p>DATE: MAR 2004</p>				<p>CWD-040-2</p>					

SECTIONAL DETAIL OF SPLIT BUTT STRAP

Labels in diagram:

- SQUARE HEAD THREADED STEEL PLUG
- 10"
- 5" DIA THREADED STL COUPLING AND STL PLUG, PRESSURE CLASS 150 PSI
- 1/4"
- TOP OF SPLIT BUTT STRAP
- WELD STL PLUG AFTER INSPECTION
- Ø HANDHOLE
- 30°
- ID OF BUTT STRAP EQUALS
- OD OF CYL OF MAINLINE PIPE PLUS 1/16" FOR 14" AND SMALLER NOMINAL PIPE AND PLUS 1/8" FOR LARGER THAN 14" NOMINAL PIPE
- T = 3/16" : 8" Ø THRU 24" Ø
- T = 1/4" : 30" Ø THRU 42" Ø
- Ø HANDHOLE
- 30°
- A

SECTION A-A


FIELD WELDED CLOSURE

Labels in diagram:

- MORTAR COATING
- 13 GA WELDED WIRE MESH
- T
- STEEL CYLINDER
- MORTAR LINING
- ID OF CYLINDER
- ID OF PIPE
- 2.5"
- 5"
- 2.5"

FIELD—APPLY STIFF CLASS C CEMENT MORTAR COATING, PER "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION" SEC 201-5.1, REINFORCED WITH 2" x 4" x 13 GA WELDED WIRE MESH

PIPE SIZE	HANDHOLES
8" THROUGH 12"	1
14" THROUGH 18"	2
20" THROUGH 42"	4




WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL FLANGED OUTLET
4" THROUGH 20"



APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 3
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 2
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 1
 APPROV. _____
 CHECK _____
 DATE 03-04
 DRAWN WEF
 0



SECTIONAL DETAIL OF OUTLET

NOMINAL OUTLET DIA (in)	MINIMUM "t _r " (in)	HUB FLANGE	
		"C" (in)	"A" (in)
4	0.237	7 1/2	9
6	0.280	9 1/2	11
8	0.322	11 3/4	13 1/2
10	0.366	14 1/4	16
12	0.375	17	19

NOTES:


- 1.) SEE MAINLINE PIPING DRAWING FOR POSITION AND USE OF OUTLET.
- 2.) STEEL HUB FLANGE CLASS D AS PER AWWA STD. C207-86.
- 3.) SEE MAINLINE PIPING DRAWING FOR MINIMUM DESIGN THICKNESS "t_r".
- 4.) "w" AND "T", REINFORCEMENT PLATE DIMENSIONS FOR OUTLET JOINTS, TO BE DESIGNED PER AWWA MII, 13.3-13.6, OR EQUAL TO MANUFACTURERS REINFORCING GUIDE.
- 5.) "t_y" = MAINLINE CYLINDER THICKNESS.
- 6.) "t_r" = REQUIRED MAINLINE CYLINDER THICKNESS.
- 7.) "t_y" = BRANCH CYLINDER THICKNESS.
- 8.) "t_r" = REQUIRED BRANCH CYLINDER THICKNESS.
- 9.) "L" = $\frac{\text{NOMINAL DIA}}{2} + 12"$

WATER
 DISTRIBUTION & TRANSMISSION
 CONSTRUCTION METHODS

TYPICAL FLANGED TANGENT OUTLET
 4" THROUGH 12" DIAMETER



0	DRAWN	WEF	DATE	03-04	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.
---	-------	-----	------	-------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------



WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL THREADED OUTLET
1" THRU 2 1/2" DIAMETER



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING


DATE: MAR 2004

CWD-340

0	DRAWN WEF	DATE 03-04	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.


WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL MANWAY FOR LARGE
PIPELINES



CROSS-SECTION OF MANWAY A-A

HEX HEAD NUTS AND BOLTS IN ACCORDANCE WITH THE SPECIFICATIONS.



CROSS SECTION OF BOLT ASSEMBLY B-B

- NOTES:
- 1.) PAINT ALL EXPOSED INTERIOR & EXTERIOR METAL SURFACES OF FLANGES, EXCEPT GASKET SURFACE, PER SPECIFICATIONS.
 - 2.) 150 LB. HUB FLANGES SHALL BE USED IF WORKING PRESSURE 175 PSI OR LESS, 300 LB. FLANGES SHALL BE USED IF WORKING PRESSURE OVER 175 PSI.
 - 3.) REINFORCE MANWAY IN ACCORDANCE WITH AWWA M11 OR EQUAL, MANUFACTURER'S REINFORCING GUIDE.
 - 4.) MANWAY STATIONS MAY BE VARIED IN ORDER TO LOCATE THE 24" DIA OPENING @ MIDPOINT IN INDIVIDUAL PIPE LENGTHS THUS PERMITTING THE MANUFACTURE OF A UNIVERSAL PIPE LENGTH.
 - 5.) PAINT UNDERSIDE OF BLIND FLANGE WITH EPOXY PER SPECIFICATIONS.

ID	FLANGE OD	BC	T	BOLT DIA	NO. BOLTS	PIPE SIZE
24"	32"	29 1/2"	1 1/4"	1 1/4"	20	24" TO 30"
30"	38 3/4"	36"	1 3/8"	1 1/4"	28	36" & LARGER

Technical drawing of a hydrant assembly. The drawing includes a side view and a top view. Key dimensions and callouts include:

- 10' MIN DISTANCE**: Dimension between the hydrant and the AC PVMT.
- 18"**: Dimension from the hydrant head to the centerline of the AC PVMT.
- HYDRANT HEAD ① OR ②**: Callout to the hydrant head.
- 3" MIN 6" MAX**: Dimension for the hydrant head height.
- FINISH GRADE**: Indicated by a dashed line.
- AC PVMT**: Air Cylindrical Pressure Vessel Main Tank.
- "V" DIMENSION**: Vertical dimension from the hydrant head to the top of the hydrant body.
- ADD 1' CTF**: Add 1 foot of CTF (Cylindrical Tank Filling).
- HOLD BACK COATING 18"**: Dimension for the hold back coating.
- SHIP FLANGE LOOSE**: Callout to the ship flange.
- WELD JOINT (TYP)**: Callout to the weld joint.
- ANCHOR BLOCK 4 CU FT**: Callout to the anchor block.
- ADD 2' CTF**: Add 2 feet of CTF.
- HOLD BACK COATING 2'-6"**: Dimension for the hold back coating.
- BEARING BLOCK PER CWD-030**: Callout to the bearing block.
- "H" DIMENSION**: Horizontal dimension from the hydrant head to the centerline of the AC PVMT.
- NOMINAL OD / 2 + 12"**: Dimension for the nominal OD.
- SHIP LOOSE**: Callout to the ship loose.
- WATER MAIN**: Callout to the water main.


NOTES:

- 1.) STANDARD OR SUPER HYDRANT PER PLANS AND SPECIFICATIONS.
- 2.) BREAK-OFF BOLTS REQUIRED BETWEEN HYDRANT AND FLANGE PER SPECIFICATION.
- 3.) HYDRANT OUTLETS SHALL FACE STREET.
- 4.) TOP OF HYDRANT BLOW-OFF TO BE PAINTED BLUE #315-15 BY FULLER O'BRIEN CO. OR DEPARTMENT APPROVED EQUAL.
- 5.) WELD ALL NON-MECHANICAL JOINTS.
- 6.) "H" AND "V" DIMENSION AS SHOWN ON PLANS

① HOLD BACK COATING 6"

BILL OF MATERIALS

ITEM	QUANTITY	REFERENCE
① STANDARD HYDRANT : 1- 2 1/2", 1- 4"	1	CWD-700
② SUPER HYDRANT : 2 - 2 1/2", 1 - 4"	1	CWD-700
③ 6" FLANGED RW GATE VALVE	1	CWD-500
④ 6" SLIP-ON WELD FLANGE (6-HOLE)	1	
⑤ 6" ML&C STEEL PIPE 10 GA, 6 5/8" OD 1/2 CML, 3/4" CMC	1	
⑥ DELETED		
⑦ 8" GATE BOX CAP, GALV SPLIT-SLEEVE, AND 12 GA STL PIPE	1	CWD-515
⑧ 6" 90° ELL	2	
⑨ 6" FLANGE	3	
⑩ 6" FLANGED OUTLET	1	CWD-300

[illegible]

- (A) ANCHOR AND BEARING BLOCKS PER CWD-030
- (B) STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS
- (C) WELD ALL PIPE JOINTS 360°
- (D) HOLD BACK COATING 6"

8" BLOW-OFF
BELOW GRADE
WITH LESS THAN 10' OF COVER

BILL OF MATERIALS


ITEM	QUANTITY	REFERENCE
(1) 30" MANHOLE COVER & RIM 30" ID CONC MANHOLE SECTION	1	CWD-811
(2) 1" MIPT X MIPT BALL CORP STOP & 1" BRASS CAP	1	CWD-500
(3) 8" FLANGED RW GATE VALVE	1	
(4) 8" SLIP-ON WELDED FLANGE	4	
(5) 8" ML&C STL PIPE 10 GA, 8 5/8" OD 1 1/2" CML, 3/4" CMC	VARIABLE	
(6) 8" BLIND FLANGE W/1" IPT TAP	1	
(7) 10" GATE BOX CAP, GALV SPLIT-SLEEVE, AND 12 GA STL PIPE	VARIABLE	CWD-515
(8) 8" 90° ELL	4	
(9) 8" FLANGED OUTLET	1	CWD-300

NOTES:

- (A) STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS
- (B) WELD ALL PIPE JOINTS 360°
- (C) HOLD BACK COATING 6"


NOTES:

- (A) STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS
- (B) WELD ALL PIPE JOINTS 360°
- (C) HOLD BACK COATING 6"



BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
① 4" THROUGH 12" MAIN	1	PER PLAN
② MAIN SIZE MJ CAP W/ 2" TAP IPF	1	PER PLAN
③ 2" x 12" BRASS NIPPLE	1	
④ 2" BRONZE VALVE, IPF, PER SPEC	1	
⑤ 2" 90° ELL SW x IPM	1	
⑥ 2" x 30"± COPPER PIPE, HARD, NO JOINTS	VARIABLE	
⑦ 2" ADAPTER SW x IPF	1	
⑧ 2" BRASS PLUG, IPM	1	
⑨ 10" GATE BOX CAP AND SPLIT SLEEVE	1	CWD-515
⑩ 10" DIA, 12 GA, STEEL PIPE	VARIABLE	
⑪ 1" SQ NUT FOR 2" VALVE AS REQUIRED	1	SUPPLIED BY CITY
⑫ MAIN SIZE GRIP RING KIT	1	

	CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING	DATE: MAR 2004	CWD-411-A
---	---	----------------	-----------



[illegible]

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
① 4" THROUGH 12" MAIN	1	PER PLAN
② MAIN SIZE MJ CAP WITH 2" TAP IPF	1	PER PLAN
③ 2" ADAPTER IPM x SW	1	
④ 2" X 12" COPPER PIPE, SOFT	1	
⑤ 2" 90° ELL SW x SW	1	
⑥ 2" COPPER PIPE, HARD DRAWN	VARIABLE	
⑦ 2" 90° BRASS ELL IPM x SW	2	
⑧ 2" BRONZE VALVE, FIPT, PER SPEC	1	
⑨ 2" COPPER PIPE, HARD (NO JOINTS)	VARIABLE	
⑩ 2" ADAPTER SW x IPF	1	
⑪ 2" BRASS PLUG IPM	1	
⑫ 10" GATE BOX CAP & SPLIT SLEEVE	1	CWD-515
⑬ 10" DIA STEEL SLEEVE (VARIES)	VARIABLE	
⑭ 1" SQ NUT FOR 2" VALVE AS REQUIRED	1	SUPPLIED BY CITY
⑮ MAIN SIZE GRIP RING KIT	1	

CWD-411-B

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0

MINIMUM LENGTH OF PIPE WITH RESTRAINED JOINTS REQUIRED TO RESTRAIN PIPE SHALL BE DESIGNED BY ENGINEER AND SHOWN ON PLANS.



BILL OF MATERIALS	
	QUANTITY
① 6" THROUGH 10" WATER MAIN	PER PLAN
② MJ END CAP WITH 2" TAP	1
③ 2" GALV 90° STREET ELL (IPT)	2
④ 2" GATE (IPT)	1
⑤ 2" GALV COUPLING (IPT)	1
⑥ 2" x 30"± GALV PIPE (IPT)	1
⑦ 2" x 24"± GALV PIPE (IPT)	1
⑧ 2" IPF x 2 1/2" MHT BUSHING	1
⑨ 2 1/2" HOSE CAP	1
⑩ 2" x 12"± GALV NIPPLE (IPT)	1
⑪ MAIN SIZE GRIP RING KIT	1

NOTES:

- 1.) CONTRACTOR SHALL LEAVE END CAP IN PLACE UNTIL FINAL CONNECTION BY CITY FORCES

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

6" THROUGH 10"
TEMPORARY CONSTRUCTION END CAPS
FOR FLUSHING, TESTING, & CHLORINATION

APPROV.	CHECK	DATE	DRAWN	3
APPROV.	CHECK	DATE	DRAWN	2
APPROV.	CHECK	DATE	DRAWN	1
APPROV.	CHECK	DATE	DRAWN	0

MINIMUM LENGTH OF PIPE WITH RESTRAINED JOINTS REQUIRED TO RESTRAIN PIPE SHALL BE DESIGNED BY ENGINEER AND SHOWN ON PLANS.

END OF WATER MAIN STATION AS SHOWN ON PLANS

24" MIN

TEMPORARY RISER

TEMPORARY

3/4 INCH CRUSHED ROCK

BILL OF MATERIALS	
ITEM	QUANTITY
① 12" WATER MAIN	PER PLAN
② 12" MJ END CAP WITH 4" ECCENTRIC TAP (IPT)	1
③ 4" x 12" GALV STEEL PIPE (IPT)	2
④ 4" GALV STEEL PIPE (IPT)	6 LF ±
⑤ 4" VALVE (FIPT), PER SPECIFICATIONS	1
⑥ 4" x 90° GALV STEEL ELL (FIPT)	2
⑦ 4" GALV END CAP (FIPT)	1
⑧ MAIN SIZE GRIP RING KIT	1
⑨ METER VAULT PER SPECIFICATIONS	1


NOTES:

1.) CONTRACTOR SHALL LEAVE END CAP IN PLACE UNTIL FINAL CONNECTION BY CITY FORCES

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

12" TEMPORARY CONSTRUCTION END CAP
FOR FLUSHING, TESTING, & CHLORINATION

0	DRAWN	DATE	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.
	WEF	03-04																	



BILL OF MATERIALS		
	QUANTITY	REF
(1) ML&C STEEL OR DIP WATER MAIN	PER PLAN	
(2) 1" THREADED OUTLET	1	CWD-340
(3) 1" MIPT x MIPT BALL CORP STOP	2	
(4) 1" GALV STEEL COUPLING	2	
(5) 1" PVC ADAPTER	2	
(6) 1" PVC PIPE	VARIES	
(7) 1" BRASS CAP	1	
(8) 10" GATE BOX AND SPLIT-SLEEVE	1	CWD-515

NOTES:

- 1.) CONTRACTOR SHALL REMOVE VALVE BOX, CLOSE AND CAP 1" BALL CORP STOP, AND REMOVE PVC RISER FOLLOWING ACCEPTANCE OF THE TRANSMISSION MAIN.
- 2.) STATION, LOCATION AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS.

(A) DOUBLE-STRAP SERVICE SADDLES SHALL BE USED ON ALL DIP CONNECTIONS

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TEMPORARY
WATER SAMPLER



PLAN VIEW
NOT TO SCALE

SECTION A-A
NOT TO SCALE

BILL OF MATERIALS


ITEM	QUANTITY
1 WATER SAMPLER HOUSING	1
2 1" COPPER TUBING (SEE DWG)	1
3 3/4" COPPER TUBING	1
4 3/4" BALL VALVE	1
5 3/4" MPT x CTS ADAPTER	1
6 3/4" x 3" NIPPLE	1
7 1" ANGLE METER STOP	1
8 1" x 3/4" METER ADAPTER	1
9 3/4" MPT x S/W ADAPTER	1
10 1/4" MPT x CTS ADAPTER	1
11 1/2" x 1/4" BRASS BUSHING	1
12 3/4" x 1/2" BRASS BUSHING	1
13 1/4" COPPER TUBING (12" MIN)	1
14 METER BOX, BROOKS 37	1
15 NO. 3 REBAR	1

DETAILS:

- 180° OPENING LID**
- 10 GA STL TUBE, OD = 8.625" (SAMPLER HOUSING)**
- CONCRETE PAD W/ WEAKENED PLANE JOINTS**
- 1/4" x 4" FELT**
- BACK OF CURB**
- CURB FACE**
- FLOW**
- EX C&G**
- CONCRETE VAULT**
- OD = 22.75" x 15.75"**
- SUPPLY LINE FROM WATER MAIN TO SAMPLING STATION**
- EX GRADE LINE**
- CONCRETE PAD**
- METER BOX**
- 1" COPPER TUBING, SOFT**
- 3/4" COPPER TUBING, SOFT FIELD FAB. 90° BEND**
- LID**
- FLUSH**
- GRAVEL**
- 1/4" x 4" FELT, (360°)**
- CONCRETE PAD (CLASS 520-C-2500)**
- WATER SAMPLER HOUSING, (FILL W/ PEA GRAVEL)**
- 4 - 1/2" DRAIN HOLES AT QUADRANTS**
- 17"±**
- 11.375"**
- 9"**
- 12"**
- 9"**
- 3.215"**
- 4"**
- 6"**
- 9"**
- 4"**
- 3'-7.25" MIN**
- 3" (TYP)**
- 4"**
- 4"**
- 1'-10" MIN**
- 90°**
- 18"**
- 36"**
- 30"**
- HINGE**
- HANDLE**
- HANDLE AND HASP FOR PADLOCK**
- SAW CUT EX SIDEWALK**
- EX CONCRETE SIDEWALK**

NOTES:


- (A) APPLY "CONCRETE GLUE" TO EX CUT CONCRETE TO PROVIDE ADHESION AND JOINT SEAL.
- (B) ATTACH FELT TO BACK OF CURB WITH CONCRETE NAILS.
- * SAMPLER HOUSING SHALL BE FUSION EPOXY COLOR COATED "SAFETY BLUE" INSIDE AND OUT.
- ** 90° DEFLECTION AT METER STOP REQUIRED ONLY FOR SAMPLERS LOCATED AT CURB FACE OR EDGE OF PAVEMENT.

[illegible]

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
① 2" IPT OUTLET	1	CWD-340
② 2" BRONZE MIPTxMIPT BALL CORP STOP	1	
③ 2" BRASS STREET ELL	1	
④ 2" TYPE K COPPER PIPE (SOFT)	VARIABLE	
⑤ 2" SW x IPM BRONZE ADAPTER	1	
⑥ 2" BRONZE GATE VALVE NRS	1	CWD-500
⑦ 2" SW x SW 90° ELL	1	
⑧ 2" HARD DRAWN COPPER PIPE, TYPE K	VARIABLE	
⑨ 2" UNIVERSAL AIR VALVE	1	
⑩ 2" GALV STREET ELL - SEE NOTE A	2	
⑪ 8" GATE VALVE CAP, GALV SPLIT SLEEVE, & 12 GA STL PIPE	1	CWD-515
⑫ 1/4" BRASS GATE VALVE, 1/4" BRASS PLUG, 1/4" x 2" BRASS NIPPLE, 1/4" BRASS STREET ELL	1 EA	
⑬ 2"ø x 6" NIPPLE	1 EA	
⑭ 2" SW x IPF BRONZE ADAPTER	1 EA	

TYPICAL 2" AIR VALVE INSTALLATION

0	DRAWN	WEF
DATE	03-04	
CHECK		
APPROV.		
1	DRAWN	
DATE		
CHECK		
APPROV.		
2	DRAWN	
DATE		
CHECK		
APPROV.		
3	DRAWN	
DATE		
CHECK		
APPROV.		



NOTES:

- (A) STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS.
- (B) BREAK-OFF BOLTS, CADMIUM-PLATED OR GALVANIZED. INSTALL WITH NUT ON TOP AND COUNTER-BORE, PACKED WITH SILICONE.
- (C) BEARING BLOCK SHALL NOT REST ON MAIN AND SHALL BE NOTCHED ON BOTH SIDES PER CWD-500
- (D) HOLD BACK COATING 18"

BILL OF MATERIALS

ITEM	QUANTITY	REFERENCE
(1) 6" FLANGED OUTLET	1	CWD-300
(2) 6" 90° ELL F/F	1	
(3) 6" RW GATE VALVE F/F	1	CWD-500
(4) 6" ML&C STL PIPE, 10 GA 6" ID, 5/16" CML, 3/4" CMC	VARIABLE	
(5) 6" - 90° WELD ELL	1	
(6) 6" WELD FLANGE, SHIP FLG LOOSE	6	
(7) 6" COMBINATION AIR VALVE, PER SPEC	1	
(8) 8" GATE BOX CAP, GALV SPLIT-SLEEVE, AND 12 GA STL PIPE	1	CWD-515
(9) FLANGE INSULATION KIT AS REQUIRED PER SPECIFICATIONS	1	
(10) 1/2" BRASS GV, 1/2" x 2" BRASS NIPPLE, 1/2" BRASS STREET ELL, 1/2" BRASS PLUG	1 EA	
(11) 6" DIA X 12" STL SPOOL, PE X PE, ML & NO COATING	1	

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

**TYPICAL 6" AIR VALVE
INSTALLATION**



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWINGS

DATE: MAR 2004

CWD-462

2'-0"

2'-0"

1'-0" MIN

PROPERTY OR R/W LINE

GUARD POSTS PER CWD-900-A WHERE INDICATED ON PLANS

7

6

11

B 6

D 6

30" MAX

6"

8 GATE BOX

TOP OF CURB OR FINISH GROUND SURFACE

A "H" DIMENSION PER PLANS

4

ADD 1' CTF

VARIABLE 24" MIN

ADD 1' CTF

CONTINUOUS UP GRADE

2

9

1

3

4

6 D

BEARING BLOCK DESIGNED BY ENGINEER C

WATER MAIN

5

ANCHOR BLOCK DESIGNED BY ENGINEER

VARIES

PROFILE VIEW

NTS

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
1 8" FLANGED OUTLET	1	CWD-300
2 8" 90° ELL F x F	1	
3 8" RW GATE VALVE F x F	1	CWD-500
4 8" ML&C STL PIPE, 10 GA 8" ID, 5/16" CML, 3/4" CMC	VARIABLE	
5 8" - 90° WELD ELL	1	
6 8" WELD FLANGE, SHIP LOOSE	6	
7 8" COMBINATION AIR VALVE, PER SPEC	1	
8 8" GATE BOX CAP, GALV SPLIT-SLEEVE, AND 12 GA STL PIPE	1	CWD-515
9 FLANGE INSULATION KIT AS REQUIRED PER SPECIFICATIONS	1	
10 1/2" BRASS GV 1/2" x 2" BRASS NIPPLE, 1/2" BRASS STREET ELL, 1/2" BRASS PLUG	1 EA	
11 8" DIA X 12" STL SPOOL, PE X PE, ML & NO COATING	1	

NOTES:


A STATION, LOCATION, AND SPECIAL NOTES PER PLAN AND PROFILE SHEETS.

B BREAK-OFF BOLTS, CADMIUM-PLATED OR GALVANIZED. INSTALL WITH NUT ON TOP AND COUNTER-BORE, PACKED WITH SILICONE.

C BEARING BLOCK SHALL NOT REST ON MAIN AND SHALL BE NOTCHED ON BOTH SIDES PER CWD-500

D HOLD BACK COATING 18".


APPROV.	
CHECK	
DATE	
DRAWN	
3	
APPROV.	
CHECK	
DATE	
DRAWN	
2	
APPROV.	
CHECK	
DATE	
DRAWN	
1	
APPROV.	
CHECK	
DATE	03-04
DRAWN	WEF
0	



SPOKED-WHEEL DETAIL

INDICATE DISTANCE AND VALVE USE

USE	SYMBOL
MAIN	M
HYDRANT	FH
SERVICE	SVC
AIR VALVE	AV
BLOW-OFF	BO



VALVE LOCATION TIES DETAIL

NOTE:

- 1.) FOR 2" GATE AND PIPING (AND FOR ALL COPPER PIPING), THE GATE BOX MATERIAL SHALL BE NOTCHED AND BLOCKED TO CLEAR SAME.
- 2.) GATE VALVES ARE TO BE INSTALLED IN THE VERTICAL POSITION UNLESS THEY ARE DESIGNED TO OPERATE IN OTHER POSITIONS.


VALVE BOX SECTIONAL DETAIL

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

**TYPICAL VALVE BOX
FOR GATE VALVES**




APPROV.	
CHECK	
DATE	
DRAWN	3
APPROV.	
CHECK	
DATE	
DRAWN	2
APPROV.	
CHECK	
DATE	
DRAWN	1
APPROV.	
CHECK	
DATE	03-04
DRAWN	WEF
0	



SECTIONAL VIEW

INDICATE DISTANCE
AND VALVE USE

USE	SYMBOL
MAIN	M
HYDRANT	FH
SERVICE	SVC
AIR VALVE	AV
BLOW-OFF	BO



L="SWING TIE" RADIAL LENGTH IN FT


VALVE LOCATION TIES DETAIL

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL VALVE BOX
FOR BUTTERFLY VALVES



0	DRAWN	WEF	DATE	03-04	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.
---	-------	-----	------	-------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------




VALVE BOX LINER SPECIFICATIONS:

20 GA x 18" LONG GALV STL SPLIT-SLEEVE WITH 1 1/2" OVERLAP AND 1/2" LIP (FLARE) ON ONE END.

OD FOR 8" VALVE BOX = 7 3/4"

OD FOR 10" VALVE BOX = 9 3/4"




TYPICAL VALVE BOX CAP

- NOTES:**
- 1.) THIS STANDARD IS TO BE USED IN CONJUNCTION WITH STANDARD DRAWINGS CWD-500, CWD-504, AND CWD-510.


SECTIONAL DETAIL

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

TYPICAL SPLIT-SLEEVE LINER AND
CAP FOR 8" AND 10" VALVE BOX

[illegible]

APPROV.	CHECK	DATE	DRAWN	0
APPROV.	CHECK	DATE	DRAWN	1
APPROV.	CHECK	DATE	DRAWN	2
APPROV.	CHECK	DATE	DRAWN	3



TYPICAL STREET INSTALLATION

BILL OF MATERIALS	
ITEM	QUANTITY
① BRONZE DOUBLE-STRAP SERVICE SADDLE (IPT)	1
② 1" BRONZE MIPT x MIPT BALL CORP STOP	1
③ ANGLE BALL METER STOP COMPRESSION x METER COUPLING (WITH 1" x 3/4" ADAPTER FOR 3/4" METER) PER SPECIFICATIONS	1
④ 1" TUBING, SOFT COPPER, TYPE K)	VARIES
⑤ METER INSTALLED BY CITY FORCES	
⑥ METER BOX PER SPECIFICATIONS AND/OR PLANS.	1
⑦ 1" OR 3/4" COUPLINGS	
⑧ 1" FIPT x COMPRESSION ADAPTOR	1


NOTES:


- 1.) METER BOX COVER TO BE CAST IRON WHERE BOX IS IN ALLEY OR DRIVEWAY.
- 2.) CONTRACTOR SHALL INSTALL METER BOXES WITH READING HOLE AT TIME ANGLE METER STOPS ARE INSTALLED.
- 3.) CITY WILL FURNISH A TEMPORARY SERVICE METER JUMPER, PRIOR TO INSTALLING METER, UPON PAYMENT OF FEES.
- 4.) METER BOX TO BE CLEANED BEFORE NEW METER CAN BE INSTALLED BY CITY FORCES.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

1-INCH WATER SERVICE



APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 3
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 2
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN 1
 APPROV. 
 CHECK _____
 DATE 03-04
 DRAWN WEF 0



BILL OF MATERIALS	
ITEM	QUANTITY
① BRONZE DOUBLE-STRAP SERVICE SADDLE (IPT)	1
② 2" BALL CORPORATION STOP MIPT x MIPT	1
③ 2" FIPT/SW BRASS 90° ELL	1
④ 2" TYPE K COPPER PIPE (SOFT)	VARIABLE
⑤ 2" SW/SW COPPER 90° ELL	1
⑥ RISER PIPE (2" HARD DRAWN COPPER)	1
⑦ 2" ANGLE BALL METER STOP (IPF x METER FLG)	1
⑧ 2" COUPLING (COMP x MIPT)	1
⑨ 1 1/2" OR 2" METER (INSTALLED BY CITY)	1
⑩ 1 1/2" OR 2" METER FLANGE (INSTALLED BY CITY)	1
⑪ METER BOX: CONCRETE COVER 2 PC OR STEEL COVER 2 PC	1

NOTES:

- 1.) A STEEL METER BOX LID IS REQUIRED IN ALLEY OR DRIVEWAY.
- 2.) DOUBLE GASKETS SHALL BE USED ON EACH SIDE OF METER SPACER (JUMPER) UNTIL METER IS INSTALLED BY CITY.

WATER
 DISTRIBUTION & TRANSMISSION
 CONSTRUCTION METHODS

2-INCH WATER SERVICE




CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004

CWD-601

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0



PROFILE VIEW

NOTES

- 1.) PRIME AND WRAP BURIED PIPE TO 6" ABOVE GRADE WITH POLYKEN #927 AND #900, OR APPROVED EQUAL.
- 2.) CITY FORCES WILL BLIND FLANGE CONNECTION POINT. WATER INSPECTOR IS TO BE PRESENT WHEN BLIND FLANGE IS REMOVED AND DETECTOR ASSEMBLY IS INSTALLED.
- 3.) FACILITIES TO BE DISINFECTED PER SPECIFICATION 205, PART 5.
- 4.) CUSTOMER TO SWAB CONNECTING VALVES WITH 600 PPM CHLORINE WHEN MAKING CONNECTION.
- 5.) CUSTOMER TO PAINT ALL ABOVE GRADE PIPING AND DETECTOR ASSEMBLY.
- 6.) FOR 10" DETECTOR ASSEMBLY INSTALL 12" LATERAL AND PIPING. CUSTOMER TO SUPPLY 12" x 10" FLANGED REDUCERS ON BOTH SIDES OF DETECTOR ASSEMBLY.
- 7.) CONTACT CITY BACKFLOW ADMINISTRATOR FOR DETECTOR ASSEMBLY SPECIFICATION, AND FOR INSPECTION AND TESTING IMMEDIATELY AFTER INSTALLATION AT (909)351-6320.
- 8.) FOR DETECTOR ASSEMBLY CLEARANCE REQUIREMENTS REFER TO CWD-630-1 AND CWD-630-2.
- 9.) RESTRAIN ALL JOINTS WITH APPROVED RESTRAINT ASSEMBLY.

MATERIALS	
ITEM	
①	DUCTILE IRON PIPE (CLASS 350)
②	90° ELL
③	1" BALL CORPORATION STOP INLET FOR CHLORINATION POINT TO BE CLOSED AND CAPPED AFTER SUCCESSFUL DISINFECTION.
④	TEMPORARY BLIND FLANGE WITH 1" IPT TAP AND 1" BALL CORPORATION STOP FOR SAMPLE.
⑤	FLANGE X MECHANICAL JOINT ADAPTOR, AS REQUIRED.


**WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS**

**4" THRU 10" ABOVE GROUND
FIRE SERVICE**




APPROV. _____
 CHECK _____
 DATE _____
 DRAWN _____
 3
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN _____
 2
 APPROV. _____
 CHECK _____
 DATE _____
 DRAWN _____
 1
 APPROV. _____
 CHECK _____
 DATE 03-04
 DRAWN WEF
 0

NOTE: SEE CWD-620-2 FOR MATERIAL CALL-OUT.



PLAN VIEW



SECTION A-A

GENERAL NOTES:

- 1) CONTRACTOR SHALL PAINT PIPING PRIOR TO INSTALLATION OF METER.

TYPICAL DIMENSIONS				
SERVICE SIZE	A	B	C	D
3 IN.	9"	24"	29"±	11"
4 IN.	9"	24"	24±	11 1/2"
6 IN.	10 1/2"	36 1/2"	13"±	12 1/2"

CONSTRUCTION NOTES:

- 1) DRY-PACK PIPE OPENINGS.
- 2) SUPPORT COMPOUND METER ON CONCRETE PAD WITH CONCRETE BLOCK.
- 3) CONTRACTOR SHALL INSTALL ALL PIPE, FITTINGS, AND MATERIALS BETWEEN THE TAPPING GATE AND "PIPING BY CUSTOMER", INCLUDING TEMPORARY FLANGED COUPLING CONNECTION AT INFLUENT VALVE.
- 4) ADJUST VAULT AND COVER TO MEET SIDEWALK AND CURB GRADE. PAINT PER SECTION 310.
- 5) PROVIDE JOINT RESTRAINTS PER CONSTRUCTION SPECIFICATIONS.
- 6) POUR PCC 480-C-2000 CONCRETE THRUST COLLAR AGAINST WALL OF VAULT.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

3", 4" AND 6" COMPOUND METER
WATER SERVICE

APPROV.		CHECK		DATE		DRAWN		APPROV.	
3									
APPROV.		CHECK		DATE		DRAWN		APPROV.	
2									
APPROV.		CHECK		DATE		DRAWN		APPROV.	
1									
APPROV.		CHECK		DATE		DRAWN		APPROV.	
0				03-04		WEF			

BILL OF MATERIALS				
ITEM	QUANTITIES			REFERENCE
	3" METER	4" METER	6" METER	
① DIA x 18" ADAPTER, FLG x MJ	1-(4" DIA)	1	1	
② GATE VALVE, DIA x FLG x FLG	2-(4" DIA)	2	2	
③ DIA x 2" BRONZE SERVICE SADDLE	2-(4" DIA)	2	2	
④ WELD FLANGE x DIA	1	1	1	
⑤ 2" x 12" GALV NIPPLE	1	1	1	
⑥ 4" x 3" GALV BUSHING	2	NA	NA	
⑦ 3" x 6" GALV NIPPLE	1	NA	NA	
⑧ 2" GATE VALVE - BRONZE	3	3	3	
⑨ 4" SCREW FLANGE	2-(4" DIA)	NA	NA	
⑩ 2" BRASS PLUG	1	1	1	
⑪ COMPOUND METER, DIA x FLG x FLG	1	1	1	PUR REQ
⑫ DIA x FLANGED COUPLING ADAPTER	1	1	1	
⑬ VAULT AND COVER	1	1	1	CWD-800
⑭ STEEL PIPE, DIA x (SCHEDULE 40)	3 LNR FT CTF			
⑮ 2" HEAVY BLACK COUPLING	1	1	1	
⑯ DIA X 36" DIP SPOOL FLG x FLG	1-(4" DIA)	1	1	
⑰ 3" SCREW FLANGE	2	NA	NA	
⑱ 3/4" CRUSHED ROCK	16 CU FT			
⑲ CONCRETE PCC 480-C-2000	15 CU FT			
⑳ NO. 4 REBAR	48 LNR FT±			
2" BY-PASS (ALT A)				
㉑ 2" x 90° ELL SW x MIPT	2	2	2	
㉒ 2" COPPER PIPE, SOFT	7 LNR FT ±			
㉓ 2" BRASS UNION	1	1	1	
㉔ 2" x 3" BRASS NIPPLE	2	2	2	
2" BY-PASS (ALT B)				
㉕ 2" x 90° STREET ELL	2	2	2	
㉖ 2" GALV PIPE	7 LNR FT ±			
㉗ 2" GALV UNION	1	1	1	
㉘ 2" x 3" GALV NIPPLE	2	2	2	

WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS	BILL OF MATERIALS FOR 3", 4" AND 6" COMPOUND METER WATER SERVICE
---	---

CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING	DATE: MAR 2004	CWD-620-2
--	-----------------------	------------------

CWD-621-1

0	DRAWN WEF	DATE 03-04	CHECK	APPROV. 	1	DRAWN	DATE	CHECK	APPROV.
1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.
2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
① 8" x 4" TEE MJ X MJ	2	
② 4" - 90° ELL B X B	2	
③ 4" RW GATE VALVE B X B	1	
④ 4" DI PIPE	16 FT±	
⑤ 8" FLG X MJ ADAPTER	2	
⑥ 8" GATE VALVE F X F	2	
⑦ 6" STL PIPE (SCHEDULE 40)	1 FT	
⑧ 6" WELD FLANGE	1	
⑨ 6" BLIND FLANGE W/2" IPT TAP	1	
⑩ 2" X 12" GALV NIPPLE	1	
⑪ 8" FLANGED COUPLING ADAPTER	1	
⑫ 8" COMPOUND METER	1	
⑬ VAULT AND COVER	1	CWD-801
⑭ 2" BRASS PLUG	1	
⑮ 8" STL PIPE (SCHEDULE 40)	7 FT±	
⑯ 8" WELD FLANGE	1	
⑰ CONCRETE PCC 480-C-2000	20 CU FT±	
⑱ 3/4" CRUSHED ROCK	28 CU FT	
⑲ NO 4 REBAR	64 FT±	
⑳ 8" DI PIPE	2 FT	
㉑ 8" GATE BOX MATERIAL	1	CWD-500
㉒ 2" GATE VALVE - BRONZE	1	

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

BILL OF MATERIALS FOR
8" FMCT WATER SERVICE



APPROV.	CHECK	DATE	DRAWN	3
APPROV.	CHECK	DATE	DRAWN	2
APPROV.	CHECK	DATE	DRAWN	1
APPROV.	CHECK	DATE	DRAWN	0

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
(1) 12" x 6" TEE F/F *	2	
(2) 6" 90° ELL RT	2	
(3) 6" RW GATE VALVE B/B	1	
(4) 6" DI PIPE	20 FT±	
(5) 12" x 10" REDUCER F/F	2	
(6) 10" GATE VALVE F/F	2	
(7) 12" FLG X MJ ADAPTER	2	
(8) 6" F/B ADAPTER	2	
(9) 10" STL PIPE (SCHEDULE 40)	10 FT±	
(10) 2" BRONZE GATE VALVE	1	
(11) 10" FLANGE COUPLING ADAPTER	1	
(12) 10" COMPOUND METER	1	
(13) VAULT AND COVER	1	CWD-802
(14) 2" BRASS PLUG	3	
(15) 2" X 12" GALV NIPPLE	1	
(16) 6" BLIND FLG W/2" IPT TAP	1	
(17) CONCRETE PCC 480-6-2000	40 CU FT	
(18) 3/4" CRUSHED ROCK	40 CU FT	
(19) NO 4 REBAR	64 FT±	
(20) 10" x 18" DIP SPOOL, F/F	ALTERNATE FOR STEEL	
(21) 8" GATE BOX MATERIAL	1	
(22) 6" STL PIPE (SCHEDULE 40)	1	
(23) 6" WELD FLG	1	

* 12" x 12" TEE F/F WITH 12" x 6" REDUCER
MAY BE USED INSTEAD OF 12" x 12" x 6" TEE.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

BILL OF MATERIALS FOR
10" COMPOUND WATER SERVICE



REGULAR FIRE HYDRANT SUPER FIRE HYDRANT


OUTLET ORIENTATION DETAIL
NTS

Labels in drawing: STREET STRIPING, REFLECTIVE HYDRANT MARKER, PAVEMENT, 6" (UNSTRIPED STREET), 18", FIRE HYDRANT ① OR ②, 3" MIN 6" MAX, 10', SEE NOTE #5, 3' MIN COVER, THRUST BLOCK, BEARING BLOCK, ⑦ GATE BOX, ③, ④, ⑤, ⑥, ⑧.

NOTES

- 1.) REGULAR OR SUPER HYDRANT IN ACCORDANCE WITH PLAN AND SPECIFICATIONS.
- 2.) BREAK-OFF BOLTS REQUIRED BETWEEN FIRE HYDRANT AND FLANGE IN ACCORDANCE WITH SPECIFICATIONS. INSTALL WITH NUT ON TOP.
- 3.) DI BURY AND FIRE HYDRANT FLANGE SHALL BE 6-HOLE.
- 4.) FIRE HYDRANT OUTLETS SHALL FACE STREET.
- 5.) FIRE HYDRANT VALVE SHALL BE A MINIMUM OF 10 FEET FROM HYDRANT.
- 6.) THRUST AND BEARING BLOCKS PER CWD-030
- 7.) FURNISH AND INSTALL A STIMSONITE MODEL 88AB TWO-WAY BLUE REFLECTIVE FIRE HYDRANT MARKER DIRECTLY OPPOSITE HYDRANT, LOCATE MARKER ON HYDRANT SIDE OF STREET CENTERLINE IN ACCORDANCE WITH THE ABOVE DETAIL, WITH REFLECTIVE SIDE FACING ONCOMING TRAFFIC, PROVIDE 2 - MARKERS FOR HYDRANTS INSTALLED AT INTERSECTIONS.
- 8.) ALL PIPE TO BE POLYETHENE-ENCASED PER SPECIFICATION SECTION 306.
- 9.) IF MAIN LINE MUST BE WET TAPPED, SEE CWD-504.

BILL OF MATERIALS		
ITEM	QUANTITY	REFERENCE
① REGULAR FIRE HYDRANT OUTLETS: 1 - 2 1/2", 1 - 4"	1	
② SUPER FIRE HYDRANT OUTLETS: 2 - 2 1/2", 1 - 4"		
③ 6" GATE VALVE, FLG/MJ, RW	1	CWD-500
④ MAINLINE X 6" TEE	1	
⑤ 6" DI BURY, FLG/MJ	1	
⑥ 6" DI PIPE	1	
⑦ 8" GATE BOX CAP, GALV SPLIT-SLEEVE, AND 12 GA STL PIPE	1	CWD-515
⑧ 6" GRIP RING	2	


[illegible]

GENERAL NOTES


- 1.) VAULT AND COVER PER SPECIFICATIONS.
- 2.) FOOTING SHALL BE POURED AGAINST UNDISTURBED SOIL, PCC 560-C-3250.
- 3.) VAULT LOCATION TO BE APPROVED BY WATER DIVISION, PUBLIC UTILITIES.
- 4.) A JOINT SEALING COMPOUND SHALL BE USED AT ALL JOINTS


WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS

NON-TRAFFIC VAULT FOR 3" THRU 6" COMPOUND METERS

[illegible]

CWD-801

0	DRAWN WFF	DATE 03-04	CHECK	APPROV. 	1	DRAWN	DATE	CHECK	APPROV. 2	DRAWN	DATE	CHECK	APPROV. 3	DRAWN	DATE	CHECK	APPROV.
---	--------------	---------------	-------	--	---	-------	------	-------	--------------	-------	------	-------	--------------	-------	------	-------	---------



WATER DISTRIBUTION & TRANSMISSION CONSTRUCTION METHODS

NON-TRAFFIC VAULT FOR 10" COMPOUND METERS

BLIND FLANGE WITH 1" IPT TAP AND 1" BALL CORP VALVE AND BRASS CAP

ALHAMBRA FOUNDRY MANHOLE FRAME AND COVER A-1252, OR A-1251-6, DIAMOND TREAD, AS REQUIRED, (OR APPROVED EQUAL)

A.C. PAVEMENT

6"

20"

FLANGED BLOW-OFF RISER

VARIES

9" MIN

6"

9"

15" 10 1/2" 10 1/2" 15"

SECTIONAL PROFILE

FILL WITH GROUT (TYP)

GRADE RING AS REQUIRED

#5 WIREHOOPS @ 6" CC (TYP)

PRE-CAST MANHOLE SEE SECTION A-A BELOW

(560-C-3250)

3/4" CRUSHED ROCK

FOOTING POURED IN FIELD AGAINST UNDISTURBED OR WELL-COMPACTED BASE PER SPECIFICATION

REINFORCE FOOTING WITH #5 BAR, BEND INTO 32" x 32" SQ

#5 BAR FOOTING REINF

INSIDE EDGE OF FOOTING

INSIDE EDGE OF MANHOLE

OUTSIDE EDGE OF MANHOLE

OUTSIDE OF FOOTING-EDGE OF EXCAVATION

OUTSIDE EDGE OF MANHOLE LID

TIE (TYP)

TIE (TYP)

30" ID FOR 12" PIPE & SMALLER

36" ID FOR 14" PIPE & LARGER


SECTION A-A

PRE-CAST MANHOLE SECTION SPECIFICATIONS:

- 1) DESIGN LOADING H = 20 - S 16
- 2) CEMENT: TYPE II, ASTM C150, 3250 PSI
- 3) REINFORCEMENT: GRADE 40 OR GRADE 60 ASTM A615
- 4) COVER TO BE DIAMOND-TREAD FINISH, LETTERED "CWD"

BLOW-OFF MANHOLE INSTALLATION

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0



SECTIONAL VIEW

NOTES:

- 1.) NUMBER AND POSITION OF GUARD POSTS AS SPECIFIED ON PLANS.
- 2.) REFER TO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION", SEC. 210 AND SEC. 310.

**WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS**

4" DIA. GUARD POST INSTALLATION



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004

CWD-900-A


SECTIONAL VIEW

NOTES:

- 1.) NUMBER AND POSITION OF GUARD POSTS AS SPECIFIED ON PLANS.
- 2.) REFER TO "STANDARD SPECIFICATIONS PUBLIC WORKS CONSTRUCTION", SEC 210 AND 310.

2.5" DIA. GUARD POST INSTALLATION

APPROV.	CHECK	DATE	DRAWN	3	APPROV.	CHECK	DATE	DRAWN	2	APPROV.	CHECK	DATE	DRAWN	1	APPROV.	CHECK	DATE	DRAWN	0



NOTES

- 1.) FLANGE INSULATION GASKETS SHALL BE FULL-FACED, NEOPRENE-COATED FABRIC-REINFORCED PHENOLIC, 1/8 INCH THICK. A ONE-PIECE SLEEVE AND WASHER, SEPARATE PHENOLIC WASHER, AND TWO CADMIUM-PLATED STEEL WASHERS SHALL BE USED FOR EACH BOLT OR CAP SCREW.
- 2.) FLANGE KITS SHALL BE FURNISHED IN ACCORDANCE WITH THE SPECIFICATIONS.
- 3.) TEST LEAD CONNECTIONS AND LOCATIONS IN ACCORDANCE WITH CWD-922.
- 4.) TEST LEADS SHALL BE TAGGED AND/OR COLOR-CODED EAST/WEST OR NORTH/SOUTH OF VALVE.
- 5.) TEST LEAD INSULATION KIT SHALL BE STRIPPED BACK ONE INCH FROM ENDS.
- 6.) WHEN FLANGE KITS ARE SPECIFIED: SIZE_____ - 150# - TYPE EN-DW.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS


FLANGE INSULATION
AND TEST LEAD INSTALLATION



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004

CWD-923



NOTES:

1. STEEL BONDING CLIP SPECIFICATIONS:
MATERIAL SPECIFICATION ASTM A356 COMMERCIAL QUALITY
CUT LENGTH = $2\frac{1}{2}" + \frac{1}{8}"$, WIDTH = $1\frac{1}{4}" + \frac{1}{8}"$.
2. LYTHERM FILLER STRIP DIMENSIONS TO BE $1" \times 1\frac{1}{2}"$
IN ORDER TO OVERLAP SIDES OF CLIP.
3. CRIMP BONDING CLIP OVER FILLER AT POINT "A" TO
COMPRESS FILLER.

PERFORMANCE NOTE:

THE ADDED FLEXIBILITY OF THE BONDING CLIP ($\frac{3}{4}"$ + MOVEMENT TOLERANCE) SIGNIFICANTLY REDUCES THE CHANCES OF WELDS BREAKING, AS OPPOSED TO THE RIGID "S"-BAR.

PIPE SIZE	JUMPERS/JOINT
16" THRU 24"	2
24" THRU 54"	3


MILD STEEL JOINT BOND

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

JOINT BOND
DETAILS

0	DRAWN WEF	DATE 03-04	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.

60"



CITY OF RIVERSIDE

ANOTHER

PUBLIC UTILITIES PROJECT

(STREET NAME)

(DIA.) WATER (DISTRIBUTION OR TRANSMISSION) MAIN

(STREET NAME) TO (STREET NAME)

PROJECT DURATION: (DATE) THRU (DATE)

CONTRACTOR IS:

(COMPANY NAME)

PHONE: (COMPANY PHONE NUMBER)

THANK YOU FOR YOUR PATIENCE!

FOR INFORMATION, PLEASE CALL: (909) 826-5285

NOTIFICATION SIGN NOTES:


- 1). SIGN DIMENSIONS ARE TO BE 48" HIGH X 60" WIDE. DIMENSION LETTERS AS SHOWN ABOVE WITH CENTERED TEXT.
- 2). SIGN SHALL BE BLUE LETTERS ON WHITE BACKGROUND WITH RPU LOGO IN YELLOW AND BLUE ON WHITE BACKGROUND.
- 3). SIGNS SHALL BE POSTED A MINIMUM OF ONE WEEK PRIOR TO CONSTRUCTION.
- 4). SIGN SHALL BE POSTED AT EACH END OF THE PROJECT AND LOCATIONS TO BE APPROVED BY THE ENGINEER PRIOR TO ERECTING THE SIGNS.
- 5). SEE CWD-960-2 FOR CONSTRUCTION OF SIGN.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

NOTIFICATION SIGN



0	DRAWN	WEF	DATE	03-04	CHECK	APPROV.	1	DRAWN	DATE	CHECK	APPROV.	2	DRAWN	DATE	CHECK	APPROV.	3	DRAWN	DATE	CHECK	APPROV.
---	-------	-----	------	-------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------	---	-------	------	-------	---------



CONSTRUCTION NOTES:

- ① 2 - DOUGLAS FIR CONSTRUCTION GRADE 4" X 4" POST.
- ② 3/4" THICK PLYWOOD.
- ③ FASTEN PLYWOOD SIGN TO POST W/6 - 5"± CARRIAGE BOLTS W/NUTS, FLAT WASHERS, AND JAM NUTS.

NOTES:

- 1) EXACT LOCATION OF SIGN TO BE DETERMINED BY ENGINEER WITH APPROVAL BY CITY PUBLIC UTILITIES DEPARTMENT.

WATER
DISTRIBUTION & TRANSMISSION
CONSTRUCTION METHODS

NOTIFICATION SIGN



CITY OF RIVERSIDE PUBLIC UTILITIES STANDARD DRAWING

DATE: MAR 2004

CWD-960-2